

BID FORM

Bid Item	Description	Unit	Quantity	Unit Price	Total Cost
Unit 1: Parking Lot					
1	Unclassified Excavation	CY	5000		
2	Embankment (Furnish/Install, Complete in Place)	CY	5000		
3	Clearing and Grubbing	AC	5		
4	6" Concrete Pavement (Furnish/Install, Complete in Place)	SY	19000		
5	4" Concrete Sidewalk (All Types) (Furnish/Install, Complete in Place)	SF	5000		
6	Hydrated Lime (6" at 33lb/SY) (Parking Lots & ADA Accessible Routes)	TON	356		
7	6" Lime Treatment (Parking Lots & ADA Accessible Routes))	SY	19800		
8	Cement (6" at 43lb/SY) (Parking Lots & ADA Accessible Routes)	TON	396		
9	6" Cement Treatment (Parkings Lots & ADA Accessible Routes)	SY	19800		
10	Stabilized Access Road & Laydown Area (Furnish/Install and Remove)	SY	4750		
11	ADA Ramp (Furnish/Install, Complete in Place)	EA	30		
12	3441.4003 Furnish/Install Alum Sign Ground Mount City Std.	EA	12		
13	4" SLD Pvmt Marking HAS (W)	LF	10000		
14	Parking Lot Legend Handicap	EA	12		
15	Precast Concrete Wheelstops (Furnish/Install, Complete in Place)	EA	12		
16	Erosion and Sediment Control Devices (Furnish/Install and Remove)	LS	1		
17	3341.0301 30" HDPE Pipe	LF	190		
18	3341.0204 24" HDPE Pipe	LF	17		
19	3349.5001 10' Curb Inlet	EA	2		
20	3349.1005 30" Flared Headwall, 1 pipe	EA	1		
21	3137.0104 Medium Stone Riprap, dry	SY	17		
22	Light Pole Assemblies (Furnish/Install, Complete in Place)	EA	38		
23	Light Pole Foundations (Furnish/Install, Complete in Place)	EA	38		
24	Lighting Pull Boxes (Furnish/Install, Complete in Place)	EA	8		
25	Lighting Conduit & Cable (Furnish/Install, Complete in Place)	LS	1		
26	Security System (Furnish/Install, Complete in Place)	LS	1		
27	Irrigation System (Furnish/Install, Complete in Place)	LS	1		
28	Landscaping & Plantings (Furnish/Install, Complete in Place)	LS	1		
29	Mobilization (3%)	LS	1		
30	Insurance	LS	1		
31	Bonds	LS	1		
32	General Conditions (5%)	LS	1		
Total - Unit 1: Parking Lot					